

State of Kansas



FORM CP-2

JOHN CARLIN  
R. C. LOUX  
JANE T. ROY  
PHILLIP R. DICK  
CAROL J. LARSON

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To be filed by Plugging Agent)

Dear Sir:

Mr. Bell Trulls of Kelso Logging Pulling has this date requested permission to plug the following described well:

Operator's Full Name: D. N. B. Drilling Inc.

Complete Address: 515 R.H. Harvey Bldg. Wichita Kansas 67202

Lease Name: Millers Well No. Y-1

Location: C-NE-NW Sec. 5 Twp. 27S Rge. 19W (E) (W)

County: Kiowa Total Depth: 4840'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereafter indicated: abandoned oil well

Mr. Trulls was instructed to plug the well as follows:

There is 363' of 8 5/8" surface casing cemented with 225 lbs and 4839' of 4 1/2" production pipe in hole cemented with 200 lbs of 50/50 pure cement. The perforations are from 4775' to 4806'. 1st plug sand off bottom hole to 4700' with 1/2 lbs cement. 2nd plug 100' with 5 lbs hulls 5 lbs Jell and 70 lbs cement. 3rd plug 5' with 5 lbs hulls + 2 lbs Jell then release rubber plug to 360' then 40 lbs cement following rubber plug. 4th plug 40' to 0' with 1 lbs hulls + 10 lbs of cement. Plugging accomplished by Halliburton Cementing Co. out of Great Bend Kans There was 2430' of oil recovered. Shut in pressure at 650 lbs

Very truly yours,

RECEIVED  
STATE CORPORATION COMMISSION

Paul Luthis  
Conservation Division Agent

NOV 17 1981  
11-17-81  
CONSERVATION DIVISION  
Wichita, Kansas