



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

11-4-81

VERBAL PERMIT FORM
(To be filed by Plugging Agent)
15-097-20820-0000

RECEIVED
STATE CORPORATION COMMISSION
NOV 10 1981

Dear Sir:

Mr. Jack Foy of Abercrombie Drilling Co. Conservation Division
Wichita, Kansas

date requested permission to plug the following described well:

Operator's Full Name: F. G. F. Petroleum Corp.

Complete Address: 209 East William St. Wichita Kansas 67202

Lease Name: Rice Well No. A-2

Location: C-SW-5W Sec. 31 Twp. 27S Rge. 18W (E) (W)

County: Kiowa Total Depth: 4890'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Foy was instructed to plug the well as follows:

There is 432' of 8 1/2" surface casing cement circulated. The anhydrite was topped at 1178'. 1st plug 1100' with 70 sbs of cement. 2nd plug pushed rubber plug to 420' then put 40 sbs cement on top of it. 3rd plug at 40' to 0' with 10 sbs cement on solid bridge. They pumped 5 sbs in rat hole & 5 sbs in water well. Plugging accomplished by Halliburton Co. out of Pratt Kans.

Very truly yours,

Paul Luttie
Conservation Division Agent