

State of Kansas



FORM CP-2

JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

10-March 1982

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

~~15-093-29758~~

RECEIVED
STATE CORPORATION COMMISSION
3-16-82
MAR 16 1982
CONSERVATION DIVISION
Wichita, Kansas

Dear Sir:

Mr. Garland Basey of Leben Drilling Co., Inc. has this date requested permission to plug the following described well:

Operator's Full Name: Commonwealth Petroleum, Inc.

Complete Address: 555 N. Woodlawn Suite 114 Wichita Kansas 67208

Lease Name: Sturgen Well No. 1

Location: C-NE-SW Sec. 35 Twp. 27 Rge. 18 (E) (40)

County: Kiowa Total Depth: 4880'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Basey was instructed to plug the well as follows:

There is 294' of 8 5/8" surface casing cement circulated. The anhydrite was topped at 1350', 1st plug 1300' with 60 sbx of cement. 2nd plug push rubber plug to 280' with 35 sbx of cement pumped on top of it. 3rd plug 40' to 0' with 10 sbx of cement. Then circulated 10 sbx of cement in rat hole & 5 sbx of cement in mouse hole and 3 sbx of cement in water well. The plugging was pumped through drill pipe with hole full of heavy mud and accomplished by Dowell Cementing.

Very truly yours,

Paul A. Luttich
Conservation Division Agent