

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION

DEC 9 1963  
 12-9-63

CONSERVATION DIVISION

WICHITA, KANSAS

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Dear Sir:

Mr. F. L. Copeland of Western Petroleum Co. Inc. has this date requested permission to plug the following described well:

Mr. Copeland guarantees payment of the plugging fee.

Operator's full Name: Pan-Western Petroleum Inc.

Complete Address: 521 Petroleum Bldg., Wichita, Kansas

Lease Name: Woods Well No. # 1

Location: C S/2 SE Sec. 24 Twp. 27 Rge. 18 (E) (W) W

County Kiowa Total Depth 5136 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Copeland was instructed to plug the well as follows:

302' of 8 5/8" surface pipe, cemented with 275 sacks.

Fill hole with drilling mud to 275', 1st cementing plug,

bridge with hulls, cement with 25 sacks. Fill hole with

drilling mud to 40', 2nd cementing plug, bridge with hulls,

cement with 10 sacks to base cellar. Bridge and cement rat

hole with 2 sacks.

Very truly yours,

Archie Elving  
 Conservation Division Agent