

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-189-20437-00-01  
Spot: SEWNNE Sec/Twnshp/Rge: 12-35S-35W  
1281 feet from N Section Line, 1482 feet from E Section Line  
Lease Name: MUDD TRUST Well #: 1  
County: STEVENS Total Vertical Depth: 6470 feet

Operator License No.: 35062  
Op Name: WICHITA WATER, LLC  
Address: PO BOX 848  
LEVELLAND, TX 79336

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1750		
CIBP		3178		WITH 2 SX CMT
PROD 4.5		6470	0	WITH 150 SX CMT
SURF 8.625		1711		WITH 600 SX CMT

Well Type: SWD UIC Docket No: D28314.0 Date/Time to Plug: 07/30/2015 8:30 AM

Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY

Proposal Rcvd. from: JOHN Company: GLOBE Phone:

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

KCC WICHITA  
AUG 05 2015  
RECEIVED

Plugging Proposal Received By: KEN JEHLIK

Witness Type: COMPLETE (100%)

Date/Time Plugging Completed: 07/30/2015 12:00 PM

KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 3178' WITH 2 SX CMT. CIBP @ 1750' OVER CASING LEAKS. PERFORATE 4 HOLS AT 1740'. RUN TBG & PACKER TO 1271'. INJECTION RATE 2 1/2 BPM @ 100# INTO PERFS AT 1740'. PUMP 45 SX CMT, 100# HULLS THEN 30 SX CMT. DISPLACE TO 1300' & PRESSURED TO 300# LEAVING 30 SX CMT INSIDE THE CASING & 45 SX CMT OUTSIDE THE CASING. PERFORATE 4 HOLES AT 600'. CIRCULATE CMT TO SURFACE WITH 175 SX CMT LEAVING THE 4 1/2" CASING & 4 1/2" X 8 5/8" ANNULUS FULL OF CMT.

Perfs:

Top	Bot	Thru	Comments
3310	3320		
3216	3246		

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

8/5/15 CKM

District: 01

RECEIVED  
JUL 31 2015  
KCC DODGE CITY

Signed

*[Signature]*

(TECHNICIAN)