

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-007-22502-00-02
Spot: S2SWSENE Sec/Twnshp/Rge: 34-33S-14W
2460 feet from N Section Line, 990 feet from E Section Line
Lease Name: ELLIS G Well #: 5
County: BARBER Total Vertical Depth: 5331 feet

Operator License No.: 33168
Op Name: WOOLSEY OPERATING COMPANY, LL
Address: 125 N MARKET STE 1000
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4964		
COND	13.375	54		WITH 60 SX CMT
PROD	4.5	5330	1825	WITH 215 SX CMT
RBP		4265		WITH 2 SX CMT
SURF	8.625	922		WITH 350 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 07/29/2015 3:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Revd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL.

KCC WICHITA
AUG 05 2015
RECEIVED

Plugging Proposal Received By: LARRY HARRIS WitnessType: NONE
Date/Time Plugging Completed: 07/29/2015 5:30 PM KCC Agent: LARRY HARRIS

Actual Plugging Report:

CASING PATCH @ 4774-4824'. RBP STUCK IN HOLE AT 4265'. PUT 2 SX CMT ON TOP OF RBP THROUGH DUMP BAILER. 1ST PLUG AT 950' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 300' WITH 50 SX CMT. PLUG AT 40' WITH 25 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4782	4816		MISSISSIPPIAN
4706	4756		MISSISSIPPIAN

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY.

Plugged through: CSG

8/5/15 ckm

District: 01

RECEIVED
JUL 31 2015
KCC DODGE CITY

Signed [Signature]
SA (TECHNICIAN)

UIC ✓