

4-020100

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-009-24,321 - 00-00

NW NW SE SE /4 SEC. 09, 18 S, 11 W
1280 feet from S section line
1190 feet from E section line

Operator license# 9951

Lease: Greensides Well # 1

Operator: Kirby Krier Oil, Inc.

County: Barton 108, 26

Address: P.O. Box 78A
Claflin, Kansas 67525

Well total depth 3331 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 339 feet

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: D.S. & W. Well Servicing, Inc. License# 6901

Address: P.O. Box 231 - Claflin, Kansas 67525

Company to plug at: Hour: 10:00 A.M. Day: 13 Month: January Year: 2000

Plugging proposal received from: Kirby Krier

Company: Kirby Krier Phone: 316-587-3810

Were: Ordered out 240 sxs 60/40 pozmix - 10% gel - 500# hulls.
Open hole abruckle 3329' - 3331'.
Cut casing off at 2100'.

Plugging Proposal Received by: Herb Deines
Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 1:30 P.M., Day: 13, Month: January, Year: 2000

Actual plugging report: 8 5/8" set at 339' w/175 sxs. 5 1/2" set at 3329' w/125 sxs cmt.
Sanded back to 3280' and topped with 5 sxs cement with dump bailer.
Cut casing off at 2100'.
Pulled casing to 1380' - tied onto and spotted 125 sxs with 300# hulls.
Pulled casing to 670' - tied onto and pumped 25 sxs with 100# hulls.
Pulled casing to 250' - tied onto and circulated cement with 70 sxs cement and 100# hulls.
Pulled casing out of the hole.
Topped off hole with 10 sxs cement.

Remarks: Allied Cementing.
Condition of casing(in hole): GOOD X BAD Anhy.plug: YES X NO
Bottom plug(in place): YES X, CALC , NO Dakota plug: YES X, NO
Plugged through TUBING , CASING X Elevation: 1777 GL

I did[X] / did not[] observe the plugging.

INVOICED

DATE 1/18/00

WV. NO. 061123

RECEIVED Jay Fisher
STATE CORPORATION COMMISSION (agent)

JAN 18 2000

CONSERVATION DIVISION
Wichita, Kansas

Form CP-2/3

R