

4-020130

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-009-00,002-0000

SE SW SW /4 SEC. 15, 18 S, 11 W
330 feet from S section line
4290 feet from E section line

Operator license# 4767

Lease: Drew A-P Well # 3

Operator: Ritchie Exploration, Inc.

County: Barton 108.91

Address: P.O. Box 783188
Wichita, Kansas 67278-3188

5/17

Well total depth 3351 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 292 feet

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Mike's Testing & Salvage, Inc. License# 31529

Address: P.O. Box 467 - Chase, Kansas 67524-0209

Company to plug at: Hour: 2:30 P.M. Day: 17 Month: May Year: 2000

Plugging proposal received from: Mike Kelso

Company: Mike's Testing & Salvage, Inc. Phone: 316-938-2943

Were: Ordered out 245 sxs 60/40 pozmix - 10% gel - 400# hulls.

Prod Perfs at 2852' - 2857'; 3037' - 3051'; 3123' - 3130'; 3210' - 3216'.

Shot casing off at 1600'.

Well drilled October 1947.

RECEIVED
STATE CORPORATION COMMISSION

MAY 22 2000

Plugging Proposal Received by: Bruce Basye

Plugging operations attended by agent? All , Part , None

CONSERVATION DIVISION
WICHITA, KANSAS

Completed: Hour: 4:45 P.M., Day: 17 Month: May, Year: 2000

Actual plugging report: 8 5/8" set at 292' w/125 sxs cement. 5 1/2" set at 3330' w/250 sxs cement. Sanded off to 2800' and topped with 5 sxs cement using a dump bailer.

Shot off casing at 1600'.

Pulled casing to 1380' - tied onto and pumped 125 sxs with 200# hulls.

Pulled casing to 600' - tied onto and spotted 50 sxs with 200# hulls.

Pulled casing to 280' - tied onto and circulated cement with 65 sxs.

Pulled casing out of the hole.

Hole standing full of cement.

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD BAD

Bottom plug(in place): YES , CALC , NO

Plugged through TUBING , CASING . Elevation: 1788 GL

I did / did not observe the plugging.

Jay P. [Signature]
(agent)

INVOICED
DATE 5/25/00
INV. NO. 61786

Form CP-2/3

(R)