

4-020146

15-009-16519-0000

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15- - Complete in 1945

SE SW NW /4 SEC. 03 , 18 S, 14 W
2970 feet from S section line
4290 feet from E section line

Operator license# 5310

Lease: Eveleigh P Well # 1

Operator: Four-Way Operating, Inc.

County: Barton

Address: P.O. Box 698
Great Bend, Kansas 67530

8/2

Well total depth 3383 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 844 feet

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Four-Way Operating, Inc. License# 5310

Address: P.O. Box 698 - Great Bend, Kansas 67530

Company to plug at: Hour: 2:00 P.M. Day: 2 Month: August Year: 2000

Plugging proposal received from: Jim Rockhold

Company: Four-Way Operating, Inc. Phone: 316-792-2506

Were: Ordered out 275 sxs 60/40 pozmix - 10% gel - 600# hulls.
CIBP at 3342'.
Prod. Perfs at 3154' - 3328'.
Well records show well had been cemented top to bottom.
Fluid Level 1700'.

Plugging Proposal Received by: Jay Pfeifer
Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 3:30 P.M., Day: 2 Month: August, Year: 2000

Actual plugging report: 8 5/8" set at 844'. 5 1/2" set at 3378'.
Tied onto 5 1/2" and pumped 225 sxs cement with 600# hulls.
Max. P.S.I. 500#. S.I.P. 500#.

RECEIVED
STATE CORPORATION COMMISSION

AUG - 8 2000
8-8-2000

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Allied Cementing.
Condition of casing(in hole): GOOD X BAD Anhy.plug: YES X NO
Bottom plug(in place): YES X, CALC , NO Dakota plug: YES X, NO
Plugged through TUBING , CASING X. Elevation: 1907 GL

I did[X] / did not[] observe the plugging.

Jay Pfeifer
(agent)

INVOICED
DATE 8/10/00
INV. NO. 1060354

Form CP-2/3
MB