

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-007-21651-00-01  
Spot: NWNENE Sec/Twnshp/Rge: 2-32S-11W  
4784 feet from S Section Line, 734 feet from E Section Line  
Lease Name: CHAPIN TED SWD Well #: 1  
County: BARBER Total Vertical Depth: 5236 feet

Operator License No.: 5050  
Op Name: HUMMON CORPORATION  
Address: PO BOX 365  
MEDICINE LODGE, KS 67104

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4992		WITH 2 SX CMT
DVT		1326		CMT TO SURFACE
PROD	4.5	5060	0	WITH 100 SX CMT
SURF	8.625	221		WITH 215 SX CMT

Well Type: SWD UIC Docket No: D23205.0 Date/Time to Plug: 07/17/2015 10:15 AM  
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION  
Proposal Rcvd. from: TYLER BELL Company: HUMMON CORPORATION Phone: (620) 930-2645

Proposed Plugging Method: CIBP @ 5010' WITH 2 SX CMT. RUN 1" DOWN BACKSIDE 4 1/2" X 8 5/8" TAG & CMT CIRCULATE TO SURFACE. RUN TBG TO 600' & CIRCULATE TO SURFACE.

Plugging Proposal Received By: SCOTT ALBERG WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 07/17/2015 11:45 AM KCC Agent: SCOTT ALBERG

Actual Plugging Report:

SET CIBP @ 4992' WITH 2 SX CMT. RAN 1" BETWEEN 8 5/8" & 4 1/2", TAGGED AT 75'. CIRCULATE CMT TO SURFACE WITH 30 SX CMT. RUN 2 3/8" TBG TO 600'. CIRCULATE TO SURFACE WITH 60 SX CMT. PULL TBG & TOP OFF WITH 10 SX CMT. HOLE STAYED FULL.

Perfs:

Top	Bot	Thru	Comments
5060	5236		

KCC WICHITA  
7-30-2015  
JUL 30 2015  
RECEIVED

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed



(TECHNICIAN)

RECEIVED  
JUL 22 2015  
KCC DODGE CITY

JA

UIC ✓