

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-057-20050-00-00
Spot: NE Sec/Twnshp/Rge: 26-28S-21W
4020 feet from S Section Line, 1326 feet from E Section Line
Lease Name: SMITH A Well #: 1
County: FORD Total Vertical Depth: 5057 feet

Operator License No.: 31938
Op Name: INDIAN OIL CO., INC.
Address: PO BOX 209 2507 SE US 160 HWY
MEDICINE LODGE, KS 67104

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4925		WITH 2 SX CMT
PROD	5.5	5048	2935	WITH 150 SX CMT
SURF	8.625	562		WITH 300 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 07/08/2015 8:30 AM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: BARRY WALTERS Company: ALLIANCE WELL SERVICE INC. Phone: (620) 672-9100

Proposed Plugging Method: SET CIBP @ 4940' WITH 2 SX CMT. PLUG AT 1415' WITH 10 SX GEL & 50 SX CMT. PLUG AT 600' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER Witness Type: PARTIAL
Date/Time Plugging Completed: 07/09/2015 8:40 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

7/7/15: SET CIBP @ 4925' WITH 2 SX CMT. RAN TBG TO 1425' & PUMPED 10 SX GEL & 50 SX CMT. NO RETURNS, BUT FLUID CAME TO ABOUT 80' FROM SURFACE. PULLED TBG TO 608' & PUMPED 50 SX CMT. NO RETURNS BUT FLUID CAME TO ABOUT 20' FROM SURFACE. PULLED TBG & LET CMT SET. 7/8/15: TAGGED CMT AT 1531'. RAN TBG TO 1425' & PUMPED 50 SX COMMON CMT WITH 3% CC. LET CMT SET & TAGGED AT 1321'. RAN TBG TO 608' & PUMPED 50 SX COMMON CMT WITH 3% CC. A RIG HAND CHECKED THE WRONG CMT SAMPLE & THEY UNKNOWINGLY RAN THE TAG THROUGH THE 608' PLUG THAT WASN'T HARDENED YET & TAGGED CMT AT 1321'. RAN TBG TO 780' & PUMPED 100 SX COMMON CMT & HAD CIRCULATION. PULLED TBG & LET SET OVERNIGHT. 7/9/15: TAGGED CMT AT 185'. RAN TBG TO 65' & CIRCULATED CMT TO SURFACE WITH 50 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5019	5029		
5008	5011		
4992	4998		

KCC WICHITA
7-30-2015
JUL 30 2015
RECEIVED

Remarks: **COMPLIANCE ISSUE: NOV TA LTR SENT** USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

8/5/15 CKM

District: 01

Signed Eric MacLaren
(TECHNICIAN)

RECEIVED
JUL 22 2015
KCC DODGE CITY

SA