

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-009-24454-00-00  
Spot: W2W2W2 Sec/Twnshp/Rge: 7-20S-11W  
2471 feet from S Section Line, 4941 feet from E Section Line  
Lease Name: KOCH Well #: 1  
County: BARTON Total Vertical Depth: 3332 feet

Operator License No.: 6039  
Op Name: L. D. DRILLING, INC.  
Address: 7 SW 26TH AVE  
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3329		125 SX
SURF	8.625	341		250 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/09/2015 9:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KASSELMAN Company: L D DRILLING Phone: (620) 793-3051

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement. Well has a liner ran to bottom of casing at 3329'.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 07/09/2015 2:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 1350', 550' and 275'. Ran tubing to 3200' and pumped 125 sx cement. Pulled tubing to 1350' and pumped 30 sx cement. Pulled tubing to 900' and pumped 30 sx cement. Pulled tubing to 600'. Circulated cement to surface on casing with 40 sx cement. Shut in casing and circulated cement to surface on surface pipe and liner with 80 sx cement. Pulled tubing and topped off with 20 sx cement.

GPS: 38.32602 -098.58934

Perfs:

Top	Bot	Thru	Comments
3324	3330		
3305	3332		

Received  
KANSAS CORPORATION COMMISSION  
JUL 31 2015  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: COPELAND ACID AND CEMENTING

Plugged through: TBG

8/5/15 CKM

District: 04

Signed Bruce Rodie  
(TECHNICIAN)

CM

JUL 14 2015