

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-24725-00-00
Spot: SWSESE Sec/Twnshp/Rge: 3-19S-15W
330 feet from S Section Line, 990 feet from E Section Line
Lease Name: WEAVER Well #: 1
County: BARTON Total Vertical Depth: 3725 feet

Operator License No.: 6039
Op Name: L. D. DRILLING, INC.
Address: 7 SW 26TH AVE
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3722		150 SX
SURF	8.625	934		450 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 07/15/2015 9:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KASSELMAN Company: L D DRILLING Phone: (620) 793-3051

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/15/2015 2:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

CIBP at 1822'. Perforated at 1450' and 300'. Ran tubing to 1805' and pumped 60 sx cement. Pulled tubing to 900' and pumped 30 sx cement. Pulled tubing to 450'. Circulated cement to surface with 50 sx cement on casing. Shut in casing and circulated cement to surface on surface pipe with 50 sx cement. Pulled tubing. Cement was at surface.

GPS: 38.42077 -098.96249

Perfs:

Top	Bot	Thru	Comments
1853	1958		
1830	1840		

Received
KANSAS CORPORATION COMMISSION
JUL 31 2015
CONSERVATION DIVISION
WICHITA, KS

Remarks: COPELAND ACID AND CEMENTING

Plugged through: TBG

District: 04

Signed Bruce Rodie
(TECHNICIAN)

8/5/15 CKM

CM

JUL 20 2015