

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-25727-00-00
Spot: SWNWSE Sec/Twnshp/Rge: 3-19S-15W
1650 feet from S Section Line, 2310 feet from E Section Line
Lease Name: WEAVER Well #: 2-3
County: BARTON Total Vertical Depth: 3700 feet

Operator License No.: 6039
Op Name: L. D. DRILLING, INC.
Address: 7 SW 26TH AVE
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3698	2001	210 SX
SURF	8.625	934		350 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/16/2015 11:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KASSELMAN Company: L D DRILLING Phone: (620) 793-3051

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/400 # hulls.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/16/2015 4:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sanded off perforations and topped off with cement. Cut casing at 2001'. Pulled casing to 1500' and pumped 125 sx cement w/200 # hulls. Pulled casing to 900' and pumped 40 sx cement w/100 # hulls. Pulled casing to 600' and pumped 40 sx cement w/100 # hulls. Pulled casing to 300'. Circulated cement to surface with 110 sx cement. Pulled casing and hole stayed full.

GPS: 38.42077 -098.96249

Perfs:

Top	Bot	Thru	Comments
3584	3586		
3578	3580		

Received
KANSAS CORPORATION COMMISSION
JUL 31 2015
CONSERVATION DIVISION
WICHITA, KS

Remarks: COPELAND ACID AND CEMENTING

Plugged through: CSG

8/5/15 CKM

District: 04

Signed Bruce Rodie
(TECHNICIAN)

CM

JUL 24 2015