

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-25967-00-00
Spot: NESWSENE Sec/Twnshp/Rge: 24-20S-14W
2086 feet from N Section Line, 983 feet from E Section Line
Lease Name: RUGAN FARMS Well #: 2-24
County: BARTON Total Vertical Depth: 3645 feet

Operator License No.: 6039
Op Name: L. D. DRILLING, INC.
Address: 7 SW 26TH AVE
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3642	2000	180 SX
SURF	8.625	364		350 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/20/2015 9:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KASSELMAN Company: L D DRILLING Phone: (620) 793-3051

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/400 # hulls.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/20/2015 2:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sanded off perforations and topped with cement. Cut casing at 2000'. Pulled casing to 1500' and pumped 125 sx cement w/200 # hulls. Pulled casing to 900' and pumped 40 sx cement w/100 # hulls. Pulled casing to 600' and pumped 40 sx cement w/100 # hulls. Pulled casing to 300'. Circulated cement to surface with 110 sx cement. Pulled casing and hole stayed full.

GPS: 38.29882 -098.81465

Perfs:

Top	Bot	Thru	Comments
3530	3534		

Received
KANSAS CORPORATION COMMISSION
JUL 31 2015
CONSERVATION DIVISION
WICHITA, KS

Remarks: COPELAND ACID AND CEMENTING

Plugged through: CSG

District: 04

Signed Bruce Rodie
(TECHNICIAN)

8/5/2015erm

cm

JUL 26 2015