

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-009-07291-00-01  
Spot: NWNESE Sec/Twnshp/Rge: 36-18S-11W  
2310 feet from S Section Line, 990 feet from E Section Line  
Lease Name: DOLL Well #: 3  
County: BARTON Total Vertical Depth: 3283 feet

Operator License No.: 30525  
Op Name: LANGSTON, D. S.  
Address: 310 W CENTRAL STE 202  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3267		200 SX
SURF	8	299		150 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/23/2015 2:00 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: D.S. LANGSTON Company: LANGSTON D.S. Phone: (620) 786-0874

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/150 # hulls.

Plugging Proposal Received By: BRUCE RODIE WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 07/23/2015 10:00 AM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perfs:

Junk in hole at 1375'. Will plug from 1375'. Tried to get through. Casing might have collapsed at the salt section. Perforated at 1350', 520' and 275'. Ran tubing to 1360' and pumped 70 sx cement w/100 # hulls. Pulled tubing to 700' and pumped 80 sx cement. Circulated cement to surface on casing. Tied to surface pipe and pressured up. Would not take cement.

GPS: 38.44107 -098.48405

Received  
KANSAS CORPORATION COMMISSION  
JUL 31 2015  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: COPELAND ACID AND CEMENTING

Plugged through: CSG

District: 04

Signed Bruce Rodie  
(TECHNICIAN)

8/5/15 ckm

CM

JUL 24 2015

Form CP-2/3