

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-07292-00-00
Spot: NENWSE Sec/Twnshp/Rge: 36-18S-11W
2310 feet from S Section Line, 1650 feet from E Section Line
Lease Name: DOLL Well #: 4
County: BARTON Total Vertical Depth: 3276 feet

Operator License No.: 30525
Op Name: LANGSTON, D. S.
Address: 310 W CENTRAL STE 202
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3272		200 SX
SURF	8.625	300		200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/22/2015 2:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Revd. from: D.S. LANGSTON Company: LANGSTON, D.S. Phone: (620) 786-0874

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/50 # hulls.

Plugging Proposal Received By: BRUCE RODIE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/23/2015 10:00 AM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perfs:

Perforated at 1350', 520' and 275'. Ran tubing to 2900' and pumped 10 sx gel followed by 50 sx cement w/100 # hulls. Pulled tubing to 1350' and pumped 60 sx cement w/100 # hulls. Pulled tubing to 700' and pumped 175 sx cement. Lost circulation. Shut down for the day.
07/22/2015- Tagged cement at 150'. Ran tubing to 140' and circulated cement to surface with 30 sx cement.

GPS: 38.44111 -098.48634

Received
KANSAS CORPORATION COMMISSION
7-31-2015
JUL 31 2015
CONSERVATION DIVISION
WICHITA, KS

Remarks: COPELAND ACID AND CEMENTING

Plugged through: TBG

District: 04

Signed

Bruce Rodie

(TECHNICIAN)

CM

8/5/15 CKM

JUL 24 2015