

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-055-22410-00-00  
Spot: NWNWSESE Sec/Twnshp/Rge: 35-25S-33W  
1012 feet from S Section Line, 1193 feet from E Section Line  
Lease Name: DRUSSELL F Well #: 1  
County: FINNEY Total Vertical Depth: 5352 feet

Operator License No.: 32446  
Op Name: MERIT ENERGY COMPANY, LLC  
Address: 13727 NOEL RD STE 1200  
DALLAS, TX 75240

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	1639		WITH 540 SX CMT

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/10/2015 8:00 AM  
Plug Co. License No.: 35070 Plug Co. Name: SAXON DRILLING, LP  
Proposal Rcvd. from: JAMES CARTER Company: MERIT ENERGY Phone: (972) 628-1558

Proposed Plugging Method: 1ST PLUG AT 1880' WITH 50 SX CMT. 2ND PLUG AT 1650' WITH 50 SX CMT. 3RD PLUG AT 930' WITH 50 SX CMT. 4TH PLUG AT 500' WITH 40 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. NO RAT HOLE OR MOUSE HOLE.

Plugging Proposal Received By: STEVE PFEIFER Witness Type: NONE  
Date/Time Plugging Completed: 07/10/2015 12:30 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

Perfs:

1ST PLUG AT 1901' WITH 50 SX CMT. 2ND PLUG AT 1684' WITH 50 SX CMT. 3RD PLUG AT 950' WITH 50 SX CMT. 4TH PLUG AT 518' WITH 40 SX CMT. 5TH PLUG AT 86' TO SURFACE. NO RAT HOLE OR MOUSE HOLE.

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: DP

8/5/15 CKM

District: 01

Signed

Stephen J. Pfeifer  
(TECHNICIAN)

51A

KCC WICHITA

JUL 24 2015

RECEIVED

RECEIVED  
JUL 10 2015  
KCC DODGE CITY