

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-159-21749-00-00  
Spot: NWNESE Sec/Twnshp/Rge: 17-20S-9W  
2284 feet from S Section Line, 1025 feet from E Section Line  
Lease Name: MELCHER Well #: 1  
County: RICE Total Vertical Depth: 3298 feet

Operator License No.: 30601  
Op Name: NORTHSTAR INVESTMENTS, INC.  
Address: 13735 PINNACLE  
WICHITA, KS 67230

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3296		125 SX
SURF	8.625	304		185 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/23/2015 9:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: JAMIE HARRIS Company: MIKE'S TESTING & SALVAGE INC. Phone: (620) 938-2943

Proposed Plugging Method: AS PER KCC RULES & REGS. THIS WELL HAD A TA - N.O.V. LETTER SENT ON.

Plugging Proposal Received By: JEFF KLOCK WitnessType: PARTIAL  
Date/Time Plugging Completed: 07/23/2015 12:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, PULL RODS AND TUBING, CK BOTTOM. SAND TO 3246' AND CAP WITH 5 SX'S CEMENT. PERFORATE AT 1200', 800', AND 355'. RUN TUBING TO 1200' AND PUMP 35 SX'S CEMENT WITH 3% CC. PULL TUBING TO 800' AND LET SET FOR 1.25 HRS. ATTEMPT TO TAG WITH SWAB BAR - COULD NOT. RUN TUBING BACK DOWN TO 1200' AND PUMP ANOTHER 35 SX'S WITH 3% CC. PULL TUBING UP TO 800' AND LET SET FOR 1.25 HRS. RUN SWAB BAR DOWN AND TAGGED CEMENT AT 1190'. PUMPED 35 SX'S AT 800', PULL TUBING TO 355' AND CIRCULATE CEMENT TO SURFACE. PULL TUBING OUT AND TOP OFF.

Perfs:

Top	Bot	Thru	Comments
3296	3298	OH	

Remarks: COPELAND TICKET #C-43393. PLUGGED DUE TO TA NOV LETTER.

Plugged through: TBG

8/5/15 CKM

District: 02

Signed Virgil Clothier  
(TECHNICIAN)

KCC WICHITA

AUG 03 2015

RECEIVED

✓