

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-193-20799-00-00
Spot: NENESWSE Sec/Twnshp/Rge: 11-10S-33W
1300 feet from S Section Line, 1392 feet from E Section Line
Lease Name: GOOSSEN TRUST 11 Well #: 1
County: THOMAS Total Vertical Depth: 4820 feet

Operator License No.: 34158
Op Name: O'BRIEN RESOURCES, LLC
Address: PO BOX 6149
SHREVEPORT, LA 71136

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4819		500 SX
SURF	8.625	347		215 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/21/2015 9:00 AM
Plug Co. License No.: 33755 Plug Co. Name: QUALITY PLUS OILFIELD SERVICES, LLC
Proposal Revd. from: HAROLD BELLERIEVE Company: O'BRIEN RESOURCES Phone: (785) 635-4531

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement, 800 # gel and 500 # hulls.
8 5/8" surface casing set at 347' w/215 sx cement. 4 1/2" production casing set at 4819' w/175 sx cement. DV tool set at 2655' w/500 sx cement. Perforations: 4681' - 4691'. TD 4820'.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/21/2015 2:30 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Ran tubing to 4650' and pumped 800 # gel followed by 70 sx cement w/250 # hulls. Pulled tubing to 2650' and pumped 90 sx cement w/100 # hulls. Pulled tubing to 1325' and pumped 95 sx cement. CWC. Pulled tubing to surface. Connected to 4 1/2" production casing and pumped 20 sx cement. Connected to 8 5/8" surface casing and pumped 20 sx cement.

GPS: 39.19465N -100.96778W

Perfs:

Top	Bot	Thru	Comments
4681	4691		

Received
KANSAS CORPORATION COMMISSION
JUL 31 2015
CONSERVATION DIVISION
WICHITA, KS

Remarks: CONSOLIDATED OIL WELL SERVICES TICKET # 47,982

Plugged through: TBG

8/5/15CKM

District: 04

Signed Darrel Dipman
(TECHNICIAN)

CM

JUL 24 2015

Form CP-2/3