

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-159-20601-00-00  
Spot: NWSESW Sec/Twnshp/Rge: 22-18S-9W  
1003 feet from S Section Line, 3624 feet from E Section Line  
Lease Name: KERN Well #: 1  
County: RICE Total Vertical Depth: 3282 feet

Operator License No.: 3911  
Op Name: RAMA OPERATING CO., INC.  
Address: 101 S MAIN ST  
STAFFORD, KS 67578

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3281	1520	375 SX
SURF	8.625	254		170 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/08/2015 9:00 AM  
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP  
Proposal Rcvd. from: RANDY GINEST Company: RAMA OPERATING Phone: (620) 546-3388

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JONATHAN HILL WitnessType: NONE  
Date/Time Plugging Completed: 07/08/2015 12:15 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. SET CIBP AT 3100' AND CAP WITH 4 SX'S CEMENT. CUT CASING OFF AT 1520' AND PULL OUT OF HOLE. RUN TUBING BACK DOWN TO 1100' AND PUMP 35 SX'S CEMENT WITH 2% CC & COTTON HULLS, PULL TUBING UP TO 850' AND LET SET AWHILE. TAGGED CEMENT WITH SAND BAILER AT 980'. PUMP 35 SX'S AT 850', PULL TUBING TO 304' AND CIRCULATE CEMENT TO SURFACE. PULL TUBING OUT AND TOP OFF.

Perfs:

Top	Bot	Thru	Comments
3247	3250	CSG	

Remarks: LOG TECH OF KS #8509. BASIC SVC'S #171812603A. THIS WELL WAS A TA - N.O.V. WELL.

Plugged through: TBG

8/5/15 CKM

District: 02

Signed Virgil Clothier  
(TECHNICIAN)

KCC WICHITA

AUG 03 2015

RECEIVED

1/5