

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-163-22921-00-00
Spot: SWSWNW Sec/Twnshp/Rge: 23-10S-20W
2970 feet from S Section Line, 4950 feet from E Section Line
Lease Name: ROGERS Well #: 1
County: ROOKS Total Vertical Depth: 3781 feet

Operator License No.: 32705
Op Name: RANEY OIL COMPANY, LLC
Address: 4665 BAUER BROOK CT.
LAWRENCE, KS 66049

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3777		150 SX
SURF	8.625	268		160 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/14/2015 9:00 AM
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC
Proposal Rcvd. from: JR HASELHORST Company: RAYNEY OIL COMPANY, LLC Phone: (785) 623-1154

Proposed Plugging Method: Ordered 525 sx 60/40 pozmix 4% gel cement and 500 # hulls.

Plugging Proposal Received By: RAY DINKEL Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/14/2015 1:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perforated: 2250', 1670' and 950'.
Ran tubing to 3750' and pumped 125 sx cement w/100 # hulls. Pulled tubing to 2445' and pumped 125 sx cement w/250 # hulls. Pulled tubing to 1205' and pumped 150 sx cement. Circulated cement to pit. POOH. Hooked to casing and pumped 50 sx cement with little pressure. Hooked to braden head and achieved pressure without moving any fluid. Topped casing off w/20 sx cement. Casing standing full.
GPS: 39.16984 -099.52984

Perfs:

Received
KANSAS CORPORATION COMMISSION
JUL 31 2015
CONSERVATION DIVISION
WICHITA, KS

Remarks: GLOBEL CEMENTING TICKET # 1735

Plugged through: TBG

8/5/15 CKM

District: 04

Signed

RAY DINKEL

(TECHNICIAN)

CM

JUL 20 2015