

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-035-24471-00-00  
Spot: SESWSNW Sec/Twnshp/Rge: 5-33S-8E  
2716 feet from S Section Line, 3608 feet from E Section Line  
Lease Name: MASSEY Well #: 5-1  
County: COWLEY Total Vertical Depth: 3050 feet

Operator License No.: 32384  
Op Name: COMANCHE RESOURCES COMPANY  
Address: 6520 N WESTERN AVE STE 300  
OKLAHOMA CITY, OK 73116

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2884		105 SX
SURF	8.625	489		250 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/11/2015 8:00 AM  
Plug Co. License No.: 35049 Plug Co. Name: QUALITY COMPLETIONS OF ARKANSAS, LLC  
Proposal Rcvd. from: BUTCH DUNKIN Company: COMANCHE RESOURCES CO. Phone: (405) 853-0959

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK WitnessType: NONE  
Date/Time Plugging Completed: 06/12/2015 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

Perfs:

RIH ON WIRELINE SET CIBP @ 2800', DUMP BAILED 2 SXS CEMENT ON TOP. RIH W/TBG @ 2750, CIRCUALTED 70 BBLS 9# VIS MUS TO SURFACE. LAYED DOWN TUBING. CUT CASING @ 555', QUAILTY COMPLETIONS CIRCUALTED 175 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCUALTED. LAYED DOWN 555' 5 1/2" CASING. TOPPED WELL BACK TO SURFACE W/CEMENT . CUT CASING 4' BELOW GROUND LEVEL & WELDED ON ID PLATE.

Remarks:

Plugged through: TBG

8/5/15 CKM

District: 02

Signed

DUANE KRUEGER  
(TECHNICIAN)

KCC WICHITA

AUG 03 2015

RECEIVED

✓