

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-035-24472-00-00
Spot: NENESENW Sec/Twnshp/Rge: 31-32S-8E
3943 feet from S Section Line, 7309 feet from E Section Line
Lease Name: HOPPY Well #: 31-1
County: COWLEY Total Vertical Depth: 3501 feet

Operator License No.: 32384
Op Name: COMANCHE RESOURCES COMPANY
Address: 6520 N WESTERN AVE STE 300
OKLAHOMA CITY, OK 73116

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3074	535	150 SX
SURF	8.625	477		250 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/10/2015 8:00 AM
Plug Co. License No.: 35049 Plug Co. Name: QUALITY COMPLETIONS OF ARKANSAS, LLC
Proposal Rcvd. from: BUTCH DUNKIN Company: COMANCHE RESOURCES CO. Phone: (405) 853-0959

Proposed
Plugging
Method:

AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK WitnessType: NONE
Date/Time Plugging Completed: 06/11/2015 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TBG @ 2900', CIRCUALTED 70 BBLs 9# 40 VIS MUD TO SURFACE. RIH ON WIRELINE SET CIBP @ 2717', DUMP BAILED 2 SXS CEMENT ON TOP. CUT CASING @ 535', QUALITY COMPLETIONS PUMPED 175 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCUALTED. LAYED DOWN 535' 5 1/2" CASING, TOPPED WELL BACK TO SURFACE W/ CEMENT. CUT & WELDED PLATE 4" BELOW GROUND LEVEL. P&A COMPLETE.

Perfs:

Top	Bot	Thru	Comments
2914	2942		CSG
2870	3876		CSG
2767	2778		CSG

Remarks:

Plugged through: TBG

8/5/15 CKM

District: 02

Signed

DUANE KRUEGER

(TECHNICIAN)

KCC WICHITA

AUG 03 2015

RECEIVED

JK