

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-195-21274-00-00
Spot: SWSENW Sec/Twnshp/Rge: 18-11S-21W
2310 feet from N Section Line, 1650 feet from W Section Line
Lease Name: STRATTON Well #: 1
County: TREGO Total Vertical Depth: 3920 feet

Operator License No.: 4656
Op Name: DAVIS PETROLEUM, INC.
Address: 7 SW 26 AVE
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3919		125 SX
SURF	8.625	291		180 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/17/2015 9:00 AM
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC
Proposal Rcvd. from: MIKE KASSELMAN Company: PROFESSIONAL PULLING SERVIC Phone: (620) 793-3051

Proposed Plugging Method: Ordered 375 sx 60/40 pozmix 4% gel cement w/500 # hulls.
Shot perforations at 285', 925', 1700' and 2250'.
Perforations: 3834' - 3852'

Plugging Proposal Received By: MARVIN MILLS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/17/2015 2:30 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3616' and pumped 75 sx cement w/200 # hulls. Pulled tubing to 2713' and pumped 100 sx cement w/100 # hulls. Pulled tubing to 1300' and pumped 150 sx cement. Good circulation of cement out of casing. Backside is full of cement. Pulled tubing out and topped off with 50 sx cement.

GPS: 39.09694 -099.69829

Perfs:

Top	Bot	Thru	Comments
3834	3852		

Received
KANSAS CORPORATION COMMISSION
JUL 31 2015
CONSERVATION DIVISION
WICHITA, KS

Remarks: SWIFT CEMENT TICKET # 28692

Plugged through: TBG

District: 04

Signed [Signature]
(TECHNICIAN)

8/5/15 CKM

CM

JUL 20 2015