

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-083-21808-00-00
Spot: N2SENE Sec/Twnshp/Rge: 1-21S-23W
1819 feet from N Section Line, 702 feet from E Section Line
Lease Name: UEHLING TRUST Well #: 1-1
County: HODGEMAN Total Vertical Depth: 4448 feet

Operator License No.: 32331
Op Name: DK OPERATING INC.
Address: 621 BENTON ST.
JETMORE, KS 67854

String	Size	Depth (ft)	Pulled (ft)	Comments
PC		1448		CEMENTED WITH 135 SX CMT. 20 SX CMT CIRCULATED TO PIT.
PROD	5.5	4447	0	WITH 125 SX CMT
SURF	8.625	220		WITH 150 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/21/2015 9:00 AM
Plug Co. License No.: 6454 Plug Co. Name: CHEYENNE WELL SERVICE, INC.
Proposal Revd. from: RICK POPP Company: DK OPERATING Phone: (785) 798-5390

Proposed Plugging Method: TBG 7 RODS ARE STUCK. TOP OF RODS @ 3475'. PUMP 20 SX CMT AT 3465' THROUGH EXISTING HOLES IN TBG. BACK OFF TBG AT 1787'. PULL TBG TO 1550' & CIRCULATE CMT TO SURFACE. PULL TBG & TOP OFF. CHECK BACKSIDE.

Plugging Proposal Received By: SCOTT ALBERG Witness Type: PARTIAL
Date/Time Plugging Completed: 07/22/2015 10:00 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

TOP OF FISH @ 3475'. TOC ON 5 1/2" IS 3230'. 7/21/15: PRESSURED THE BACKSIDE TO 500# WITH 10 SX CMT. BOTTOM-SPOTTED 20 SX CMT THROUGH TBG. BACKED TBG OFF AT 1787' & PULLED UP TO 1556'. PUMPED 165 SX CMT WITH GOOD CIRCULATION UNTIL THE LAST 10 SX. PULLED TBG & LET SET 2 1/2 HOURS. TAGGED CMT AT 1322'. RAN TBG TO 1300' & PUMPED 35 SX CMT WITH NO CIRCULATION. PULLED TBG & LET SET OVERNIGHT. 7/22/15: TAGGED TOC @ 865' WITH TBG. CIRCULATED CMT TO SURFACE WITH 90 SX CMT. PULLED TBG & TOPPED OFF WITH 10 SX CMT. HOLE STAYED FULL.

Perfs:

Top	Bot	Thru	Comments
4438	4447		
KCC WICHITA JUL 30 2015 RECEIVED			

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

8/5/15 CKM

District: 01

Signed [Signature]
(TECHNICIAN)

RECEIVED
JUL 23 2015
KCC DODGE CITY