

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-185-22451-00-00
Spot: NENWSW Sec/Twnshp/Rge: 17-22S-11W
2305 feet from S Section Line, 4388 feet from E Section Line
Lease Name: KLEPPER SW Well #: 1
County: STAFFORD Total Vertical Depth: 3700 feet

Operator License No.: 5056
Op Name: F. G. HOLL COMPANY L.L.C.
Address: 9431 E CENTRAL STE 100
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3270		WITH 2 SX CMT
CIBP		3440		
PROD	5.5	3698	0	WITH 175 SX CMT
SURF	8.625	302		WITH 125 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/15/2015 8:30 AM
Plug Co. License No.: 8253 Plug Co. Name: G & L WELL SERVICE, INC.
Proposal Rcvd. from: ADAM APLEY Company: F.G. HOLL Phone: (316) 684-8481

Proposed Plugging Method: SET CIBP @ 3270' & 2 SX CMT. PERFORATE AT 550'. RUN TBG INTO 400'. PUMP DOWN TBG WITH 15 SX GEL & CIRCULATE CMT TO SURFACE IN 5 1/2" X 8 5/8" ANNULUS & 2 3/8"/5 1/2" ANNULUS. LAY DOWN TBG & TOP OFF 5 1/2" CASING.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/16/2015 11:40 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

7/15/15: SET CIBP @ 3270' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. PERFORATE 5 1/2" AT 550'. RUN TBG TO 556'. PUMP DOWN TBG WITH 150 SX CMT. HAD RETURNS BUT CMT DID NOT CIRCULATE. SHUT DOWN OVERNIGHT TO LET CMT SET. 7/16/15: TAG TOC @ 340'. PERFORATE 5 1/2" CASING AT 310'. RUN TBG INTO 310'. PUMPED DOWN TBG WITH 125 SX CMT FILLING 5 1/2" X 8 5/8" ANNULUS & TBG/5 1/2" ANNULUS TO SURFACE WITH CMT.

Perfs:

Top	Bot	Thru	Comments
3338	3344		

KCC WICHITA
7-30-2015
JUL 30 2015
RECEIVED

Remarks: **COMPLIANCE ISSUE: NOV TA LTR SENT** USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: TBG

8/5/15 ckm

District: 01

Signed Stephen Pfeifer
(TECHNICIAN)
SA

RECEIVED
JUL 23 2015
KCC DODGE CITY