

For Imaging Only

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-23977-00-00
Spot: SWSNW Sec/Twnshp/Rge: 30-28S-8E
1340 feet from S Section Line, 4500 feet from E Section Line
Lease Name: BREEDLOVE A Well #: 1
County: BUTLER Total Vertical Depth: 3225 feet

Operator License No.: 5120
Op Name: RANGE OIL COMPANY, INC.
Address: 9412 E. CENTRAL PO BOX 781775
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3221	1500	150 SX
SURF	8.625	227		125 SX
T1	2.375	2847		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/03/2015 8:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: (620) 727-3409

Proposed Plugging Method: AS PER KCC RULES & REGS
Plug Date Exceeds

Plugging Proposal Received By: DUANE KRUEGER Witness Type: NONE *5 yr Billing cutoff*
Date/Time Plugging Completed: 07/06/2010 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TBG @ 2830', QUALITY WELL SERVICE MIXED & PUMPED 30 SXS 60/40 POZMIX 4% GEL & DISPLACED IN CASING SI #1500. TAGGED CEMENT PLUG @ 2700'. RIH ON WIRELINE CUT 5 1/2" CASING @1500', LAYED DOWN 1,500' OF 5 1/2" CASING. RIH W/TBG @ 250', QUALITY WELL SERVICE MIXED & PUMPED 105 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. TOPPED WELL BACK TO SURFACE W/5 SXS. PLUG DOWN 5:00 P.M. 7-3-2015. QUAITY WELL SERVICE TICKET #6013.

Perfs:

Top	Bot	Thru	Comments
2830	2833		CSG

Remarks:

Plugged through: CSG

District: 02

Signed DUANE KRUEGER
(TECHNICIAN)

8/5/15 CKM

KCC WICHITA

AUG 03 2015

RECEIVED

JK