

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-24045-00-00
Spot: NWNE Sec/Twnshp/Rge: 33-28S-8E
1550 feet from N Section Line, 1700 feet from E Section Line
Lease Name: FERRELL A Well #: 1
County: BUTLER Total Vertical Depth: 3097 feet

Operator License No.: 5120
Op Name: RANGE OIL COMPANY, INC.
Address: 9412 E. CENTRAL PO BOX 781775
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3089	1400	150 SX
SURF	8.625	219		130 SX

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 07/02/2015 8:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUAITY WELL SERVICE Phone: (620) 222-4304

Proposed
Plugging
Method:

AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER WitnessType: NONE
Date/Time Plugging Completed: 07/03/2015 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

SANDED BACK @ 2690', DUMP BAILED 5 SXS CEMENT ON TOP. CUT 5 1/2" CASING @ 1400', LAYED DOWN 1,400' OF 5 1/2' CASING. RIH W/TBG @ 350', QUALITY WELL SERVICE MIXED & PUMPED 110 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCUALTED. PLUG DOWN 5:00 PM 7-3-2015. QUALITY WELL SERVICE TICKET #6012.

Perfs:

Top	Bot	Thru	Comments
2753	2756		CSG

Remarks:

Plugged through: CSG

8/5/15 CKM

District: 02

Signed

Duane Krueger

(TECHNICIAN)

KCC WICHITA

AUG 03 2015

RECEIVED

VJK