

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-135-25362-00-00
Spot: NWNW Sec/Twnshp/Rge: 4-20S-24W
4456 feet from S Section Line, 4619 feet from E Section Line
Lease Name: LUNDY Well #: 4-4
County: NESS Total Vertical Depth: 4505 feet

Operator License No.: 32204
Op Name: REDLAND RESOURCES, LLC
Address: 6001 NW 23RD ST
OKLAHOMA CITY, OK 73127

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4240		WITH 2 SX CMT
CIBP		4380		
PC		1390		WITH 280 SX CMT
PROD	4.5	4502	0	WITH 175 SX CMT
SURF	8.625	216		WITH 170 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/16/2015 10:00 AM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Revd. from: DAVID HICKMAN Company: REDLAND RESOURCES Phone: (620) 253-6588

Proposed Plugging Method: SET CIBP @ 4240' WITH 2 SX CMT. PLUG 1620' WITH CMT TO 0'. CHECK BACKSIDE WITH CMT TO 500 PSI,

Plugging Proposal Received By: KENNY SULLIVAN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/16/2015 1:15 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 4240' WITH 2 SX CMT. RAN TBG TO 1661' & CIRCULATED CMT TO SURFACE WITH 130 SX CMT. PULLED TBG & TOPPED OFF WITH 15 SX CMT. PRESSURED BACKSIDE TO 500# WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4443	4450		
4430	4434		
4400	4423		
4305	4312		
4290	4294		

KCC WICHITA
7-30-2015
JUL 30 2015
RECEIVED

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

8/5/15 ckm

District: 01

RECEIVED
JUL 22 2015
KCC DODGE CITY

Signed Eric MacLaren
(TECHNICIAN)