

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-009-25449-00-00  
Spot: NESWNENE Sec/Twnshp/Rge: 13-17S-12W  
935 feet from N Section Line, 700 feet from E Section Line  
Lease Name: LAMATSCH Well #: 1  
County: BARTON Total Vertical Depth: 3360 feet

Operator License No.: 30458  
Op Name: RJM COMPANY  
Address: PO BOX 256  
CLAFLIN, KS 67525

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3353	1490	180 SX
SURF	8.625	330		180 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/17/2015 9:00 AM  
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.  
Proposal Rcvd. from: CHRIS HOFFMAN Company: RJM CO Phone: (620) 587-3600

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: BRUCE RODIE WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 07/17/2015 3:00 PM KCC Agent: BRUCE RODIE

**Actual Plugging Report:**

Sanded off perforations and topped with 5 sx cement. Shot off casing at 1490'. Pulled casing to 1400' and pumped 125 sx cement w/200 # hulls. Pulled casing to 900' and pumped 50 sx cement w/100 # hulls. Pulled casing to 600' and pumped 40 sx cement w/100 # hulls. Pulled casing to 300'. Circulated cement to surface with 100 sx cement. Pulled casing and hole stayed full.

GPS: 38.57723 -098.59269

**Perfs:**

Top	Bot	Thru	Comments
3236	3242		
3206	3210		
3164	3242		

Received  
KANSAS CORPORATION COMMISSION  
**JUL 31 2015**  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: COPELAND ACID AND CEMENTING

Plugged through: CSG

8/5/15 ckm

District: 04

Signed Bruce Rodie  
(TECHNICIAN)

CM

JUL 24 2015