

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-159-21703-00-00
Spot: NWSESW Sec/Twnshp/Rge: 19-20S-10W
692 feet from S Section Line, 3359 feet from E Section Line
Lease Name: WEBER Well #: 2-A
County: RICE Total Vertical Depth: 3585 feet

Operator License No.: 6988
Op Name: SMITH, RICHARD E. DBA SMITH OIL O
Address: 410 N. ADAMS PO BOX 550
HUTCHINSON, KS 67504

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3565		100 SX
SURF	8.625	259		200 SX
SURF		261		

Well Type: SWD UIC Docket No: D23002.0 Date/Time to Plug: 07/21/2015 11:30 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: JAMIE HARRIS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 562-0895

Proposed Plugging Method: AS PER KCC RUELS & REGS. THIS WELL HAD FAILED MIT. CASING LEAK AT 1000' - 2580'.

Plugging Proposal Received By: JEFF KLOCK WitnessType: PARTIAL
Date/Time Plugging Completed: 07/21/2015 3:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. SAND PERFS BACK TO 3390' AND CAP WITH 5 SX'S CEMENT. PERFORATE AT 1300', 900', AND 310'. RUN TUBING TO 1300' AND PUMP 35 SX'S WITH 3% CC. PULL TUBING UP TO 900' AND LET SET AWHILE. TAG CEMENT AT 1235' WITH SWAB BAR. PUMPED 35 SX'S THRU TUBING AT 900', PULL TUBING TO 310' AND CIRCUALTE CEMENT TO SURFACE. PULL TUBING OUT AND TOP OFF.

Perfs:

Top	Bot	Thru	Comments
3444	3492	CSG	

Remarks: LOG TECH OF KS. #8525. COPELAND #C-43403. PLUGGED DUE TO FAILED MIT.

Plugged through: TBG

8/5/15 ccm

District: 02

Signed Virgil Clothier
(TECHNICIAN)

KCC WICHITA

Form CP-2/3

AUG 03 2015

RECEIVED

JK

UICV