

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-163-24297-00-00
Spot: NENESWSW Sec/Twnshp/Rge: 29-8S-19W
1285 feet from S Section Line, 1190 feet from W Section Line
Lease Name: MARCOTTE Well #: 1
County: ROOKS Total Vertical Depth: 3580 feet

Operator License No.: 4787
Op Name: TDI
Address: 1310 BISON RD
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	229		150 sx

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 07/11/2015 12:00 AM
Plug Co. License No.: 33350 Plug Co. Name: SOUTHWIND DRILLING, INC.
Proposal Rcvd. from: LARRY Company: SOUTHWIND DRILLING, INC. Phone: (620) 617-3478

Proposed Plugging Method: Ordered 305 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: EDWIN SCHUMACHER Witness Type: NONE
Date/Time Plugging Completed: 07/11/2015 10:00 AM KCC Agent: EDWIN SCHUMACHER

Actual Plugging Report:

1st plug @3480 w/50 sx
2nd plug @1530 w/50 sx
3rd plug @860 w/100 sx
4th plug @280 w/50 sx
5th plug @40 w/10 sx

Rathole 30 sx Mousehole 15 sx

Perfs:

Received
KANSAS CORPORATION COMMISSION
JUL 31 2015
CONSERVATION DIVISION
WICHITA, KS

Remarks: GLOBAL
Plugged through: DP

8/5/15 ckm

District: 04 Signed Ed Schumacher (TECHNICIAN) CM

JUL 14 2015