

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-025-21216-00-00
Spot: WS2S2 Sec/Twnshp/Rge: 11-32S-22W
660 feet from S Section Line, 2820 feet from E Section Line
Lease/Unit Name: ALDRIDGE Well Number: 1
County: CLARK Total Vertical Depth: 6835 feet

Operator License No.: 31691
Op Name: CORAL COAST PETROLEUM, L.C.
Address: 200 EAST 1ST. STE 001
WICHITA, KS 67202

Conductor Pipe: Size _____ feet:
Surface Casing: Size 8.625 feet: 612
Production: Size _____ feet:
Liner: Size _____ feet:

\$222.14

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 08/28/2001 3:00 PM
Plug Co. License No.: 32453 Plug Co. Name: ACID SERVICES LLC
Proposal Rcvd. from: ROBERT THOMPSON Company: TR SERVICES Phone: _____

Proposed Plugging Method: 1ST PLUG AT 1230' WITH 50 SX CMT. 2ND PLUG AT 630' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT. 4TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 08/28/2001 4:30 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

RUN 2 3/8" TUBING IN TO SPOT PLUGS THROUGH. 1ST PLUG AT 1200' WITH 50 SX CMT. 2ND PLUG AT 630' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT. 4TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT.

Remarks: USED 60/40 POZMIX 6% GEL BY ACID SERVICES.

Plugged through: TBG

District: 01

Signed Stephen J. Pfeifer
(TECHNICIAN)

RECEIVED
AUG 31 2001
KCC WICHITA

INVOICED

DATE 8-31-01
INV. NO. 2002060320

AUG 29 2001

Form CP-2/3