

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-025-20333-00-00  
Spot: CNESE Sec/Twnshp/Rge: 13-30S-21W  
1980 feet from S Section Line, 660 feet from E Section Line  
Lease/Unit Name: BRENSING Well Number: 3-13  
County: CLARK Total Vertical Depth: 5323 feet

Operator License No.: 31938  
Op Name: INDIAN OIL CO., INC.  
Address: PO BOX 209 2507 SE US 160 HIGHWAY  
MEDICINE LODGE, KS 67104

Conductor Pipe: Size feet: 8 1/2 8173.00  
Surface Casing: Size 8.625 feet: 638 WITH 450 SX CMT  
Production: Size 4.5 feet: 5323 WITH 200 SX CMT  
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 09/20/2001 2:00 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MICHAEL FARRAR Company: INDIAN OIL Phone: (620) 886-3763

Proposed Plugging Method: SAND BACK TO 5100' & 5 SX CMT. PUMP 300# HULLS - 10 SX GEL - 50 SX CMT - 10 SX GEL - 100# HULLS - 8 5/8" WIPER PLUG - 150 SX CMT.

Plugging Proposal Received By: SCOTT ALBERG Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 09/20/2001 2:30 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PERFS AT 5140-44'. SANDED BACK TO 5100' & PUT 4 SX CMT ON TOP OF SAND BRIDGE THROUGH BAILER. PUMPED DOWN 8 5/8" SURFACE PIPE WITH 300# HULLS - 10 SX GEL - 50 SX CMT - 10 SX GEL - 100# HULLS - 8 5/8" WIPER PLUG - 150 SX CMT. MAXIMUM PRESSURE 500#. SHUT IN PRESSURE 50#.

Remarks: USED 60/40 POZMIX 6% GEL BY ACID SERVICES. RECOVERED 3800' OF 4 1/2" CASING.

Plugged through: CSG

District: 01

RECEIVED  
SEP 28 2001  
KCC WICHITA

Signed Stephen J. Pfeifer  
(TECHNICIAN)

INVOICED SEP 24 2001  
DATE 10-01-01  
INV. NO. 2002060683 MP

Form SP-2/3