

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-025-20276-00-00
Spot: CS2SE Sec/Twnshp/Rge: 13-30S-21W
660 feet from S Section Line, 1320 feet from E Section Line
Lease/Unit Name: BRENSING Well Number: 2-13
County: CLARK Total Vertical Depth: 5226 feet

Operator License No.: 31938
Op Name: INDIAN OIL CO., INC.
Address: PO BOX 209 2507 SE US 160 HIGHWAY
MEDICINE LODGE, KS 67104

Conductor Pipe: Size feet: 5 1/2
Surface Casing: Size 8.625 feet: 602 WITH 400 SX CMT
Production: Size 4.5 feet: 5224 WITH 200 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 09/20/2001 12:30 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MICHAEL FARRAR Company: INDIAN OIL Phone: (620) 886-3763

Proposed Plugging Method: SAND BACK TO 5090' & 4 SX SMT. PUMP 300# HULLS - 10 SX GEL - 50 SX CMT - 10 SX GEL - 100# HULLS - 8 5/8" WIPER PLUG - 150 SX CMT.

Plugging Proposal Received By: SCOTT ALBERG Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 09/20/2001 1:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PERFS AT 5159-5162'. SANDED BACK TO 5090' & PUT 4 SX CMT ON TOP OF SAND BRIDGE THROUGH BAILER. PUMPED DOWN 8 5/8" SURFACE PIPE WITH 300# HULLS - 10 SX GEL - 50 SX CMT - 10 SX GEL - 100# HULLS - 8 5/8" WIPER PLUG - 150 SX CMT. MAXIMUM PRESSURE 700#. SHUT IN PRESSURE 350#.

Remarks: USED 60/40 POZMIX 6% GEL BY ACID SERVICES, RECOVERED 3800' OF 4 1/2" CASING.

Plugged through: CSG

District: 01

Signed

Stephen J. Pfeifer
(TECHNICIAN)

RECEIVED

SEP 28 2001

KCC WICHITA

INVOICED SEP 25 2001

DATE

10-01-01

INV. NO.

2002060683 *MP*

Form CP-2/3