

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-025-20137-00-00

Spot: CN2S2

Sec/Twnshp/Rge: 31-30S-21W

2130 feet from S Section Line, 2585 feet from E Section Line

Lease/Unit Name: SEACAT D

Well Number: 5

County: CLARK

Total Vertical Depth: 5319 feet

Operator License No.: 5123

Conductor Pipe: Size

feet:

Op Name: PICKRELL DRILLING COMPANY, INC.

Surface Casing: Size 8.625

feet: 619

WITH 300 SX CMT

Address: 100 SOUTH MAIN - SUITE 505

Production: Size 4.5

feet: 5306

WITH 150 SX CMT

WICHITA, KS 67202

Liner: Size

feet:

3172.87

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 07/19/2001 2:40 PM

Plug Co. License No.: 31529

Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: MIKE KELSO

Company: MIKE'S TESTING & SALVAGE, INC. Phone: (620) 938-2537

Proposed
Plugging
Method:

SAND TO 4590' WITH 4 SX CMT ON TOP. 1ST PLUG AT 1200' WITH 50 SX CMT. 2ND PLUG AT 650' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE MIDDLETON

WitnessType: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 07/19/2001 4:00 PM

KCC Agent: STEVE MIDDLETON

Actual Plugging Report:

PBTD 5257'. PERFS AT 5223-5228'. SAND TO 4590' WITH 4 SX CMT ON TOP. 1ST PLUG PUMP 15 SX GEL & 50 SX CMT AT 1200'. 2ND PLUG PULL TO 650' AND PUMP 50 SX CMT. 3RD PLUG PULL TO 40' AND PUMP 10 SX CMT. STAYED FULL.

RECEIVED
KANSAS CORPORATION COMMISSION

AUG 01 2001

CONSERVATION DIVISION

INVOICE

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 3127' OF 4 1/2" CASING.

DATE 8-01-01

Plugged through: CSG

INV. NO. 2002060154

District: 01

Signed-

(TECHNICIAN)

JUL 20 2001

Form CP-2/3