

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-025-20239-00-00
Spot: CS2SWNE Sec/Twnshp/Rge: 25-30S-22W
2970 feet from S Section Line, 1980 feet from E Section Line
Lease/Unit Name: GILES B Well Number: 3
County: CLARK Total Vertical Depth: 5351 feet

Operator License No.: 5123
Op Name: PICKRELL DRILLING COMPANY, INC.
Address: 100 SOUTH MAIN - SUITE 505
WICHITA, KS 67202

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 530 WITH 300 SX CMT
Production: Size 4.5 feet: 5336 WITH 150 SX CMT
Liner: Size feet: \$ 173.91

Well Type: OIL UIC Docket No: Date/Time to Plug: 07/18/2001 3:20 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC. Phone: (620) 938-2537

Proposed Plugging Method: SAND TO 5200' & 4 SX CMT ON TOP. 1ST PLUG AT 1200' WITH 50 SX CMT. 2ND PLUG AT 560' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT. USE 15 SX GEL FOR SPACER.

Plugging Proposal Received By: STEVE MIDDLETON Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 07/18/2001 4:30 PM KCC Agent: STEVE MIDDLETON

Actual Plugging Report:

PBTD 5285'. PERFS AT 5257-5265'. SAND TO 5200' WITH 4 SX CMT ON TOP. 1ST PLUG PULL TO 1200'. PUMP 15 SX GEL & 50 SX CMT. 2ND PLUG PULL TO 560' & PUMP 50 SX CMT. 3RD PLUG PULL TO 40' & PUMP 15 SX CMT. STAYED FULL.

RECEIVED
KANSAS CORPORATION COMMISSION

JUL 23 2001

CONSERVATION DIVISION

INVOICED

DATE 7-23-01
INV. NO. 2002060118

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 3807' OF 4 1/2" CASING.

Plugged through: CSG

District: 01

Signed

(TECHNICIAN)

JUL 19 2001

Form CP-2/3