

KANSAS

FORM CP-3
Rev. 1-8-82

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-025-20575-00-0

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Picbrell Drilling Co.

Complete Address Litwin Bldg. Wichita Kans 67202

Lease Name Giles Well No. B7

Location C-SE-NW-NW Sec. 25 Twp. 30 Rge. 22 (East)(West)

County Clark Total Depth 5450'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Picbrell Drilling Co.

Address Litwin Bldg. Wichita Kansas 67202 License No. _____

Operation Completed: Hour: 5:45 P.M. Day: 11 Month: March Year: 19 82

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

The anhydrite was topped at 820'. 1st plug at 780' with 70 lbs of cement. 2nd plug at 670' with 40 lbs of cement. 3rd plug 40' to 0' with 10 lbs of cement. Then circulated 5 lbs of cement in rat hole. The cement was pumped through drill pipe with hole full of heavy mud. The plugging was accomplished by allied cementing. Mr. Steve Durant gave Mr. French these orders.

Amount of Surface Casing: 595' of 8 5/8" cement circulated with 300 lbs of cement

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Paul A. Luttich
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

I went by his well to be sure of the plugging orders on my way to a well at Protection Kans. Because I had not been with this rig for some time. But I honestly believe Mr. French will plug the well right.

Signed: Paul A. Luttich
Conservation Division Agent

INVOICED

RECEIVED STATE CORPORATION COMMISSION

DATE 3-17-82

MAR 16 1982

INV. NO. 9669-W

CONSERVATION DIVISION
Wichita, Kansas