

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-04888-00-00
Spot: SE NW SE Sec/Twnshp/Rge: 15-20S-12W
1650 feet from S Section Line, 1650 feet from E Section Line
Lease/Unit Name: BUCKBEE Well Number: 3
County: BARTON Total Vertical Depth: 3388 feet

Operator License No.: 31199
Operator Name: D J OIL OPERATIONS
Address: 305 E. 6TH
ELLINWOOD, KS 67526

Conductor Pipe: Size _____ feet:
Surface Casing: Size 8.62 feet: 180 100 SX CMT
Production: Size 5.5 feet: 3375 100 SX CMT 110.11
Liner: Size _____ feet:

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/03/2000 9:30 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC. Phone: (316) 938-2943

Proposed Plugging Method: Ordered out 350 sxs 60/40 pozmix - 10% gel.
Casing parted at 210'.

Plugging Proposal Received By: JAY PFEIFER Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 11/03/2000 1:00 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Ran wireline in the hole - TD 210'.
Rigged up on 5 1/2" - casing parted at 210'.
Pulled parted casing out of the hole.
Tripped tubing in the hole to 1433'. Allied Cementing tied onto tubing and pumped 100 sxs.
Pulled tubing to 650' and spotted 40 sxs.
Pulled up to 250' and circulated cement with 180 sxs.
Pulled tubing out of the hole.
Hole standing full of cement.

Remarks: ALLIED CEMENTING COMPANY

Plugged through: TBG

District: 04

Signed Jay Pfeifer (TECHNICIAN)

INVOICED
DATE 11/8/00
INV. NO. 2001060950

Form CP-2/3

NOV 06 2000

LEWIS DRILLING CO

#3

BUCKBEE

15-20-12W
SE NW SE

S3

Contr.

BARTON

County

E 1815 RB Comm.

Comp.

9-18-53

IP

103 BOPD

PHY POT

Tops	Depth	Datum
Ann-Top	891	+1224
Flw. Base	618	+1197
HEEB	2999	-1184
BR LM	3120	-1305
LANS	3138	-1323
GONG	3366	-1551
ARB	3372	-1557
TD	3388	-1573

Casing

8" 180

5" 3375

DST 3386; 10' MUD,
BHP 0#CO 3386: BAIL & TST,
NO OIL; DD 3388: SSO:
BAIL 1 BOPH: ACID
500; SWB 2 1/2 BOPH

BUCKBEE SW POOL

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS