

4-020133

02145-00-01

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15-009-13-0000000

SW NW SE /4 SEC. 36, 18 S, 15 W  
1650 feet from S section line  
2310 feet from E section line

Operator license# 30163Lease: Howell Well # 7Operator: Great Plains Petroleum, Inc.County: Barton 114.89

Address: 221 Circle Drive  
Wichita, Kansas 67218

Well total depth 3535 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 908 feet

Aband. oil well X, Gas well     , Input well     , SWD     , D & A     Plugging contractor: D.S. & W. Well Servicing, Inc. License# 6901Address: P.O. Box 231 - Claflin, Kansas 67525-0231Company to plug at: Hour: 12:00 P.M. Day: 24 Month: May Year: 2000Plugging proposal received from: Joseph StrubeCompany: D.S. & W. Well Servicing, Inc. Phone: 316-587-3361Were: Ordered out 210 sxs 60/40 pozmix - 10% gel - 500# hulls.Prod Perfs at 3442' - 3446'; 3396' - 3402'; 3378' - 3381'; 3259' - 3265'.Open hole at 3524' - 3535'.Cut casing off at 1950'.Well drilled in 1958.

RECEIVED

STATE CORPORATION COMMISSION

JUN 1 2000

Plugging Proposal Received by: Herb DeinesCONSERVATION DIVISION  
Wichita, KansasPlugging operations attended by agent? All ☒ , Part ☐ , None ☐Completed: Hour: 2:30 P.M., Day: 23 Month: May Year: 2000Actual plugging report: 8 5/8" set at 908' w/450 sxs cement. 5 1/2" set at 3524' w/ 70 sxs cement. Sanded off casing at 3200'.Cut casing off at 1950'.Pulled casing to 1600' - tied onto and pumped 110 sxs with 300# hulls.Pulled casing to 900' - tied onto and spotted 50 sxs with 200# hulls.Pulled casing to 250' - tied onto and circulated cement with 55 sxs.Pulled casing out of the hole.Hole standing full of cement.Remarks: Allied Cementing.Condition of casing(in hole): GOOD ☒ BAD ☐Bottom plug(in place): YES ☒ , CALC ☐ , NO ☐Plugged through TUBING ☐ , CASING ☒Anhy. plug: YES ☒ NO ☐Dakota plug: YES ☒ , NO ☐Elevation: 1901 GLI did ☒ / did not ☐ observe the plugging

INVOICED  
DATE 6/6/00  
INV. NO. 61826

Jay J. J.  
(agent)

Form CP-2/3