

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-22950-00-00
Spot: CNWSNW Sec/Twnshp/Rge: 5-19S-15W
3630 feet from S Section Line, 3630 feet from E Section Line
Lease/Unit Name: WISSMAN Well Number: 2
County: BARTON Total Vertical Depth: 3720 feet

Operator License No.: 9654 Conductor Pipe: Size _____ feet:
Op Name: SILVER EAGLE CRUDE (OHNMACHT, ST) Surface Casing: Size 8.625 feet: 1054 450 SX CMT
Address: RR 1, BOX 106B Production: Size 5.5 feet: 3718 75 SX CMT
GREAT BEND, KS 67530 Liner: Size _____ feet: _____ 120.90

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/21/2000 1:30 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC. Phone: (316) 938-2537

Proposed Plugging Method: Ordered out 280 sxs 60/40 pozmix - 10% gel - 600# hulls.
Prod Perfs at 3670' - 3674'.
Shot off at 2000'.

Plugging Proposal Received By: JAY PFEIFER Witness Type: Plugging Operations Partially Witnessed
Date/Time Plugging Completed: 12/21/2000 3:45 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Sanded back to 3600' and topped with 5 sxs cement with a dump bailer.
Rigged up on 5 1/2" and shot lose at 2000'.
Pulled up to 1650' - tied onto and pumped 100 sxs with 300# hulls.
Pulled to 1050' and spotted 40 sxs with 200# hulls.
Pulled to 650' and spotted 50 sxs with 100# hulls.
Pulled to 200' and circulated cement with 40 sxs.
Pulled casing out of the hole.
Hole standing full of cement.

RECEIVED
KANSAS CORPORATION COMMISSION

DEC 28 2000

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

CONSERVATION DIVISION
WICHITA, KS

District: 04

Signed Jay Pfeifer (TECHNICIAN)

110
INVOICED
DATE 12/29/00
WVZ NO. 20010612/6

Form CP-2/3

DEC 22 2000

REPLACEMENT CARD

ROBERT L. SHAW
P.O. BOX 65


#2 WISSMAN

5-19-15W
NW SE NW

CLAFLIN, KS 67525

CONTR WOODMAN-IANNITTI DRG. CTY BARTON

GEOLOGICAL FIELD OTIS-ALBERT



ELV 2054 KB SPD 11/6/82 CARD ISSUED 4/28/83 IP P 30 BOPD, NW
2049 GL GOR SD 3670-3674

LOG	Tops	Depth/Datum
*ANH	1054 + 1000
*B/ ANH	1080 + 974
HEEB	3280-1226
TOR	3292-1238
DOUG	3309-1255
BR LM	3349-1295
LANS	3360-1306
BKC	3583-1529
GOR SD	3668-1614
ARB	3693-1639
REAG SD	3702-1648
QTZ	3710-1656
RTD	3719-1665
LTD	3720-1666
* DRILLERS TOPS		

API 15-009-22,950

8 5/8 " 1059/450SX; 5 1/2 " 3718/75SX
NO DST'S
MCT - CO; PF (GOR SD) 3670-74 W/2 SPF, AC 300G (7.5%),
SWB LD, GSO, SET 2 3/8 " TBG AT 3669, POP, P 30 BOPD, NW

INFO RELEASED: 1/5/84 - WAS TIGHT HOLE.

COPYRIGHT 1983
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS