

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-23839-00-00
Spot: SWSENE Sec/Twnshp/Rge: 24-20S-13W
2970 feet from S Section Line, 990 feet from E Section Line
Lease/Unit Name: SCHARTZ Well Number: 1-24
County: BARTON Total Vertical Depth: 3600 feet

Operator License No.: 5030
Operator Name: VESS OIL CORPORATION
Address: 8100 E. 22ND N. BLDG. 300
WICHITA, KS 67226

Conductor Pipe: Size _____ feet:
Surface Casing: Size 8.62 feet: 306 200 SX CMT
Production: Size 4.5 feet: 3599 175 SX CMT 117.00
Liner: Size _____ feet:

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/27/2000 1:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC. Phone: (316) 938-2537

Proposed Plugging Method: Ordered out 180 sxs 60/40 pozmix - 10% gel - 500# hulls.
Prod. Perfs 3484' - 3506'; 3292' - 3294'; 3260' - 3264'; 3250' - 3252'; 3227' - 3230'; 3206' - 3210'.
Shot casing off at 1800'.

Plugging Proposal Received By: HUBERT DEINES
Date/Time Plugging Completed: 11/27/2000 2:45 PM

Witness Type: Plugging Operations 100% Witnessed (Complete)
KCC Agent: JAY PFEIFER

Actual Plugging Report:

Sanded off bottom to 3150' and topped with 5 sxs cement.
Rigged up on 4 1/2" casing and shot free at 1800'.
Pulled 4 1/2" up to 1350' and pumped 65 sxs with 200# hulls.
Pulled 4 1/2" to 700' and spotted 40 sxs with 100# hulls.
Pulled 4 1/2" to 250' and circulated cement with 55 sxs.
Pulled casing out of the hole.
Hole standing full of cement.

RECEIVED
STATE CORPORATION COMMISSION
NOV 30 2000

Remarks: ALLIED CEMENTING COMPANY

CONSERVATION DIVISION
Wichita, Kansas

Plugged through: CSG

District: 04

Signed _____

(TECHNICIAN)

INVOICED

DATE 12/1/00

INV. NO. 2001061051

Form CP-2/3

NOV 28 2000

TEXAS ENERGIES, INC.

P.O. BOX 947

#1-24 SCHARTZ

24-20-13W

SW SE NE


PRATT, KS 67124

CONTRACTOR WHEATSTATE OILFIELD SVC

CTY BARTON

GEOLOGIST RICHARD HARPER

FIELD SUNNY VALLEY SW



ELV 1856 KB SPD 2/13/84 CARD ISSUED 7/25/85 IP P 14 BO & 66 BWPD
1851 GL DRLG COMP 2/22/84 ARB 3484-3506

LOG	Tops	Depth/Datum	API 15-009-23,839
ANH		670+1186	8-5/8 " 306 / 200SX, 4 1/2 " 3599 / 175SX NO CORES
HEEB		3070-1214	DST (1) 3192-3248 (LANS) / 30-45-45-60, 700' GIP, REC 160'
TOR		3085-1229	HOCM, 330' MCO, 30' W, SIP 1001-996#, FP 92-97 / 117-161#, HP 1652-1630#
DOUG SH		3106-1250	DST (2) 3244-82 (LANS) / 30-45-45-60, 950' GIP, REC 30' HO & GCM, 30' W, SIP 1060-1060#, FP 28-53 / 78-104#, HP 1664- 1640#
BR LM		3189-1333	DST (3) 3286-95 (LKG G) / 30-45-30-30, REC 65' HO SPKD DM, SIP 943-861#, FP 14-16 / 16-25#, HP 1687-1670#
LANS		3204-1348	DST (4) 3862-80 (LKC I) / 30-30-30-30, REC 30' DM, SIP 803- 757#, FP 14-17 / 22-27#, HP 1711-1687#
CONG		3433-1577	DST (5) 3470-90 (ARB) / 30-45-45-60, REC 40' SOC GSY MUD, 120' HO & GCM, 60' HMC GSY OIL, SIP 1118-989#, IFP PLUG- GED / 81-85#, HP 1757-1730#
ARB		3476-1620	
PBDT		3599-1743	
RTD		3600-1744	
LTD		3604-1748	

(continued)

COPYRIGHT 1984
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS