

4-020148

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-009-20,771 - 00-00
W2 NW SE /4 SEC. 22, 20 S, 11 W
1980 feet from S section line
2310 feet from E section line

Operator license# 4732

Lease: Schulte Well # 1

Operator: Clay Moore

County: Barton 107.74

Address: 6440 N. Central Expwy
#620 LB 33
Dallas, Texas 75206

8/10

Well total depth 3315 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 248 feet

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Quality Well Service License# 31925

Address: P.O. Box 41 - Chase, Kansas 67524

Company to plug at: Hour: 9:00 A.M. Day: 10 Month: August Year: 2000

Plugging proposal received from: Joe Maes

Company: Quality Well Service Phone: 316-727-3410

Were: Ordered out 185 sxs 60/40 pozmix - 10% gel - 400# hulls.
Prod. Perfs at 3095' - 3110'; 3306' - 3315'.
Cut off casing at 1330'.

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All , Part , None

Completed: Hour: 11:00 A.M., Day: 10 Month: August, Year: 2000

Actual plugging report: 8 5/8" set at 248' w/250 sxs. 5 1/2" set at 3307' w/125 sxs.
Sanded back casing to 3000' and topped with 5 sxs cement using a dump bailer.
Cut casing off at 1330'.

Pulled casing to 1175' - tied onto casing and pumped 85 sxs with 300# hulls.

Pulled casing to 550' - tied onto casing and spotted 40 sxs with 100# hulls.

Pulled casing to 200' - tied onto casing and circulated cement with 45 sxs.

Pulled casing out of the hole.

Topped with 15 sxs cement.

Remarks: Acid Service, LLC

Condition of casing(in hole): GOOD BAD Anhy.plug: YES NO

Bottom plug(in place): YES , CALC , NO Dakota plug: YES , NO

Plugged through TUBING , CASING . Elevation: 1760 GL

I did / did not observe the plugging.

INVOICED

DATE 8/22/00

TRAIL NO 2001060454

RECEIVED Jay Fisher
STATE CORPORATION COMMISSION (agent)

8-14-2000
AUG 14 2000

Form CP-2/3A

CONSERVATION DIVISION
Wichita, Kansas