

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-04912-00-00
Spot: NWSESW Sec/Twnshp/Rge: 20-20S-12W
990 feet from S Section Line, 3630 feet from E Section Line
Lease/Unit Name: WELLS Well Number: 2
County: BARTON Total Vertical Depth: 3535 feet

Operator License No.: 5228
Op Name: PARRISH CORPORATION
Address: 110 SOUTH MAIN, STE 510
WICHITA, KS 67202

Conductor Pipe: Size feet: # 1 1/4 . 89
Surface Casing: Size 8.625 feet: 276 225 SX CMT
Production: Size 5.5 feet: 3534 100 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 02/28/2001 9:00 AM

Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC. Phone: (316) 938-2537

Proposed Plugging Method: Ordered out 225 sxs 60/40 pozmix - 10% gel.
Prod Perfs at 3488' - 3494'; 3453' - 3458'; 3508' - 3512'.
Casing parted at 2605'.

Plugging Proposal Received By: HERB DEINES

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 02/28/2001 12:30 PM

KCC Agent: JAY PFEIFER

Actual Plugging Report:

MIRU on 5 1/2". Sanded back to 3070' and topped with 5 sxs cement using a dump bailer.
5 1/2" casing parted at 2605'.
Pulled 5 1/2" to 1500' - pumped 100 sxs with 250# hulls.
Pulled up to 800' and spotted 50 sxs with 150# hulls.
Pulled up to 300' and circulated cement with 65 sxs.
Pulled 5 1/2" out of the hole.
Topped with 10 sxs.


RECEIVED
STATE CORPORATION COMMISSION
MAR 5 2001
CONSERVATION DIVISION
WICHITA, KANSAS
INVOICED
DATE 03-08-2001
INV. NO 2001061467

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed



(TECHNICIAN)

C-G DRLG & L K PARRISH #2 WELLS

20-20-12W NW SE SW 53

Contr. C-G DRLG BARTON County

E 1853 RB Comm. Comp. 12-22-61 IP 25 BOPD/ARB

Tops	Depth	Datum
ANH	655	+1198
HEEB	3064	-1211
BR LM	3185	-1332
LANS	3200	-1347
ARB	3438	-1585
TD	3535	-1682

Casing
 8" 277
 5" 3534
 DST 3450-65/90", 180' G, 240'
 FROGGY MDY O, BHP 620-108#/20"
 DST 3465-75/30", 20' M, BHP
 1010-110#/20"
 DST 3475-91/30", 10' M, BHP
 1010-108#/20"
 DST 3491-3520/90", 70' G, 40'
 OCM, 360' MCO, 120' OCM, TR SW,
 BATCHMAN POOL 180' OILY W,
 240' SW, BHP 1095-
 900#/20": CO 3521:
 12/3509-12: SWB 2
 BOPH/4: A 250: 9 BOPH

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

11-10-61
DATE