

4-020121

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-009-15,571-0000
NW SE NW /4 SEC. 22, 20 S, 12 W
3630 feet from S section line
3630 feet from E section line

Operator license# 5920 *4/12*
Operator: TePe Oil & Gas
Address: P.O. Box 522
Canton, Kansas 67428

Lease: Steckel Well # A-5
County: Barton *111.70*
Well total depth 3437 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 230 feet

Aband. oil well Gas well Input well SWD D & A

Plugging contractor: Mike's Testing & Salvage, Inc. License# 31529

Address: P.O. Box 467 - Chase, Kansas 67524

Company to plug at: Hour: 8:30 A.M. Day: 12 Month: April Year: 2000

Plugging proposal received from: Monte Andrews

Company: Mike's Testing & Salvage, Inc. Phone: 316-938-2943

Were: Ordered out 250 sxs 60/40 pozmix - 10% gel - 400# hulls.

Prod Perfs at 3293' - 3303'; 3375' - 3385'; 3410' - 3412'.

Cast Iron Bridge Plug at 3405'.

Spud 02-02-57.

Shot casing off at 2010'.

RECEIVED
STATE CORPORATION COMMISSION
APR 14 2000
CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All Part None

Completed: Hour: 11:30 A.M. Day: 12 Month: April Year: 2000

Actual plugging report: 8 5/8" set at 230' w/225 sxs. cement. 5 1/2" set at 3437' w/125 sxs.
Shot casing off at 2010'.

Pulled casing to 1450' - tied onto and pumped 100 sxs cement with 300# hulls.

Pulled casing to 650' - tied onto and circulated cement with 80 sxs.

Pulled casing out of hole. Topped off with 50 sxs cement.

Remarks: United Cementing and Acid Company.

Condition of casing(in hole): GOOD BAD Anhy.plug: YES NO

Bottom plug(in place): YES CALC NO Dakota plug: YES NO

Plugged through TUBING CASING Elevation 1817 GL

I did / did not observe the plugging.

INVOICED
DATE 4/18/00
INV. NO. 061605

Jay Pfeiffer
(agent)

Form 2P-2/3
R