

4-020118 15-009-15570-0000

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

02-15-57 Comp.
API Number: 15- - 01-02-57 Spud

SE NW NW /4 SEC. 22, 20 S, 12 W
4290 feet from S section line
4290 feet from E section line

Operator license# 5920
Operator: TePe Oil & Gas
Address: P.O. Box 522
Canton, Kansas 67428

Lease: Steckel Well # A-4
County: Barton
Well total depth 3448 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 253 feet

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Mike's Testing & Salvage, Inc. License# 31529

Address: P.O. Box 467 - Chase, Kansas 67524

Company to plug at: Hour: 9:00 A.M. Day: 31 Month: March Year: 2000

Plugging proposal received from: Mike Kelso

Company: Mike's Testing & Salvage, Inc. Phone: 316-938-2943

Were: Ordered out 230 sxs 60/40 pozmix - 10% gel - 400# hulls.
Prod. Perfs 3147' - 3150'; 3184' - 3188'; 3193' 3197'; 3213' - 3217'; 3228' - 3232';
3276' - 3280'; 3384' - 3388'; 3396' - 3410'; 3420' - 3426'.
Shot casing off at 2300'.
Cast iron bridge plug at 3364'.

Plugging Proposal Received by: Herb Deines
Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 12:00 P.M., Day: 31 Month: March Year: 2000

Actual plugging report: 8 5/8" set at 253' w/225 sxs. cement. 5 1/2" set at 3448' w/125 sxs.
Sanded back to 3090' and topped with 5 sxs cement with a dump bailer.
Shot casing off at 2300' and pulled to 1450'.
Tied onto casing and spotted 100 sxs cement and 300# hulls.
Pulled casing to 650' - tied onto and pumped 40 sxs cement and 100# hulls.
Pulled casing to 250' - tied onto and circulated cement with 55 sxs cement.
Pulled casing out of hole - hole standing full of cement.

Remarks: United Cementing and Acid Company.
Condition of casing(in hole): GOOD X BAD
Bottom plug(in place): YES X, CALC, NO
Plugged through TUBING, CASING X. Elevation: 1828 GL

I did [X] / did not [] observe the plugging.

Jay P. Fisher
(agent)

INVOICED RECEIVED
STATE CORPORATION COMMISSION
DATE 4/6/00 4-6-2000
INV. NO. 061521 APR 6 2000

Form CP-2/3

R

CONSERVATION DIVISION
Wichita, Kansas