

4-010462

D-06,410

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-009-30918-00-01

SE NE SE /4 SEC. 36, 18 S, 15 W
1650 feet from S section line
330 feet from E section line

Operator license# 30163

Lease: Howell Well# 6

Operator: Great Plains Petroleum

County: Barton

Address: 221 Circle Drive
Wichita, Kansas 67218

Well total depth 3686 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 882 feet

Aband. oil well Gas well , Input well , SWD X, D & A

Plugging contractor: D.S. & W. Well Service License# -

Address: _____

Company to plug at: Hour: 12:00 P.M. Day: 18 Month: May Year: 2000

Plugging proposal received from: Brian

Company: D.S. & W. Well Service Phone: -

Were: _____

RECEIVED
STATE CORPORATION COMMISSION

JUN 1 2000

CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by: Case Morris

Plugging operations attended by agent? All[], Part[], None[]

Completed: Hour: 3:00 P.M., Day: 18, Month: May, Year: 2000

Actual plugging report: Sanded to 3450' and dumped 5 sxs cement. Cut off casing at 1700'. Pulled to 1600' and pumped 110 sxs 60/40 - 10% gel cement with 300# hulls. Pulled to 900' and pumped 50 sxs cement with 200# hulls. Pulled to 250' and circulated with 60 sxs cement.

Remarks: _____

Condition of casing(in hole): GOOD BAD Anhy.plug: YES NO
Bottom plug(in place): YES , CALC , NO Dakota plug: YES , NO
Plugged through TUBING , CASING . Elevation: _____ GL

I did[] / did not[] observe the plugging. Case Morris

(agent)

INVOICED

Form CP-2/3

DATE 6/6/00

INV. NO. 61826

(R)