

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-04562-00-00
Spot: CSWSESW Sec/Twnshp/Rge: 28-19S-11W
330 feet from S Section Line, 3630 feet from E Section Line
Lease/Unit Name: SCHWAMBORN Well Number: 6
County: BARTON Total Vertical Depth: 3353 feet

Operator License No.: 5920
Op Name: TE-PE OIL & GAS COMPANY
Address: PO BOX 522
CANTON, KS 67428

Conductor Pipe: Size _____ feet: 8 108.97
Surface Casing: Size 8.625 feet: 255 175 SX CMT
Production: Size 5.5 feet: 3339 100 SX CMT
Liner: Size _____ feet: _____

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/29/2002 12:30 PM

Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC. Phone: (620) 938-2943

Proposed Plugging Method: Ordered out 250 sxs 60/40 pozmix - 10% gel - 500# hulls.
1988 old operator drilled out of the pipe at 650'.

Plugging Proposal Received By: JAY PFEIFER

Witness Type: Plugging Operations Were Not Witnessed

Date/Time Plugging Completed: 03/29/2002 4:30 PM

KCC Agent: JAY PFEIFER

Actual Plugging Report:

TIH with tubing - hit bridge at 650'.
Tied onto tubing and circulated cement with 250 sxs.
POOH. Hole full of cement.
04-01-2002 - TOC at 150' - sanded in hole and topped with cement.

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed _____

(TECHNICIAN)

RECEIVED
APR 05 2002
KCC-WICHITA

APR 02 2002

INVOICED
DATE 4-08-02
INV. NO. 2002061624

Form CP-2/3

EL DORADO REFINING #6 SCHWAMBORN 28-19-11W 53
SW SE SW

Contr. LEWIS DRILLING BARTON County

E 1783 Comm. Comp. 2-25-55 IP 235 BOPD
PHY POT

Tops	Depth	Datum
HEEB	291.9	=1136
T. OR	2931	=1148
DOUG	2949	=1166
DOUG SND	2976	=1193
BR LM	3039	=1256
LANS	3059	=1276
SH CONG	3321	=1538
ARB	3336	=1553
TD	3353	=1570

Casing
8" 255
5" 3337
DST 3062-85/33", GAS IN 3", FLO OIL IN 17", BHP 870#; DST 3119-35/1 HR, 1500' OIL, BHP 420#; DST 3139-44/1 HR, 180'; MDY OIL, 60' OIL, BHP 730#; DST 3189-3207/1 HR, 35' MUD; DST 3227-37/1 HR, 25' MUD, BHP 300#; DD 3353: 5 GF/1/2 HR; PB 3250: PERF 16/- 3134-38: 20/3121=26; ACID 2000: 1800' OIL: SWB 82 BO/1 1/2 HRS;
ANTON POOL

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS