

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-23614-00-00
Spot: W2W2E2 Sec/Twnshp/Rge: 35-19S-12W
2640 feet from S Section Line, 2310 feet from E Section Line
Lease/Unit Name: SEYFERT Well Number: 1
County: BARTON Total Vertical Depth: 3430 feet

Operator License No.: 6039
Operator Name: L.D. DRILLING, INC.
Address: RR 1 BOX 183B
GREAT BEND, KS 67530

9/14

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 278
Production: Size 5.5 feet: 3429 *111.48*
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 9/14/00 9:00:00 AM
Plug Co. License No.: 6039 Plug Co. Name: L.D. DRILLING, INC.
Proposal Rcvd. from: MIKE KASSELMAN Company: L.D. DRILLING, INC. Phone: (316) 793-3051

Proposed Plugging Method: Ordered out 300 sxs 60/40 pozmix - 10% gel - 400# hulls.
Prod Perfs @ 2929' - 2932'.
Operator backed out 746' of 5 1/2" casing. Casing fell over - could not screw back onto.

Plugging Proposal Received By: HUBERT DEINES Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 09/14/2000 10:45 AM KCC Agent: JAY PFEIFER

Actual Plugging Report:

8 5/8" set at 278' w/200 sxs. 5 1/2" set at 3429' w/150 sxs.
Ran tubing to 726' - tied onto and circulated cement w/220 sxs w/400# hulls. Pulled tubing out of the hole.
Tied onto the 8 5/8" and topped staged w/55 sxs.
Max. P.S.I. 300#. S.I.P. 100#.

RECEIVED
STATE CORPORATION COMMISSION

SEP 22 2000

Remarks: FORMERLY KNOWN AS PANNING #1 LEASE. ALLIED CEMENTING COMPANY.

Plugged through: TBG

CONSERVATION DIVISION
Wichita, Kansas

District: 04

Signed Jay Pfeifer (TECHNICIAN)

INVOICED

DATE 9/25/00

WEL. NO. 2001060742

Form CP-2/3

SEP 19 2000